

Appendix C

Ecological Management Plan



West Sussex County Council

A29 REALIGNMENT

Outline Ecological Management Plan





West Sussex County Council

A29 REALIGNMENT

Outline Ecological Management Plan

TYPE OF DOCUMENT (VERSION) PUBLIC

PROJECT NO. 70060779

OUR REF. NO. OUTLINE EMP

DATE: SEPTEMBER 2020

WSP

Mountbatten House
Basing View
Basingstoke, Hampshire
RG21 4HJ




Phone: +44 1256 318 800

Fax: +44 1256 318 700

WSP.com



QUALITY CONTROL

Issue/revision	First issue	Revision 1	Revision 2	Revision 3
Remarks	First Draft			
Date	September 2020			
Prepared by	Bradley Williams			
Signature	 Williams, Bradley (UKBDW001) 2020.10.12 14:15:50 +01'00'			
Checked by	Verity Dickie			
Signature	 Dickie, Verity (UKVXD007) 2020.10.14 14:29:43 +01'00'			
Authorised by	Adrian Hutchings			
Signature	 Hutchings, Adrian (UKARH003) I am approving this document 2020.10.14 14:39:07 +01'00'			
Project number	7006779			
Report number	Outline EMP			
File reference	\\uk.wspgroup.com\central data\Projects\700550xx\70055091 - WSCC - A29 Phase 1 Planning Application\03 WIP\10 Ecology\05 Reports\EMP			

CONTENTS

1	INTRODUCTION	1
1.1	PROJECT BACKGROUND	1
1.2	AIMS AND OBJECTIVES	1
1.3	LEGISLATION AND POLICY OVERVIEW	1
2	ECOLOGICAL BACKGROUND	3
2.1	OVERVIEW	3
2.2	ECOLOGICAL RECEPTORS	3
3	ECOLOGICAL MANAGEMENT PLAN	13
3.1	OVERVIEW	13
3.2	DESIGN MEASURES	13
	AVOIDANCE MEASURES	13
	LANDSCAPE STRATEGY	13
	LIGHTING STRATEGY	14
	DRAINAGE STRATEGY	15
	SPECIES SPECIFIC MITIGATION	16
3.3	CONSTRUCTION MEASURES	18
	GENERAL CONSTRUCTION MEASURES	18
	SPECIES SPECIFIC CONSTRUCTION MEASURES	19
3.4	ECOLOGICAL ENHANCEMENT	21
	HABITAT CREATION	21
4	CONCLUSION	22
5	REFERENCES	23



PROJECT REFERENCES	23
TECHNICAL REFERENCES	23

6 FIGURES 25

TABLES

Table 2-1 – Ecological Baseline	4
---------------------------------	---

FIGURES

Figure 1 –Scheme Location Plan	25
Figure 2 – Landscape Plan (A29-WSP-LA-GA-005)	25
Figure 3 – Indicative Ecological Mitigation	25

APPENDICES

APPENDIX A

RELEVANT LEGISLATION

1 INTRODUCTION

1.1 PROJECT BACKGROUND

- 1.1.1. West Sussex County Council (referred to as 'the Applicant') is seeking to obtain detailed planning permission for Phase 1 of the realignment of the A29 (referred to as the 'Scheme'), to the north of Eastergate and the north-west of Barnham, villages north of Bognor Regis (as shown in Figure 1).
- 1.1.2. The proposed planning application will seek permission for:
- The construction of a 1.3km single carriageway with a 3m wide shared cycleway / footway, 2.5m wide central island, four uncontrolled crossings, three roundabouts, landscaping, noise barriers and other associated works.*
- 1.1.3. The planning application boundary for the Scheme, the area which it encompasses, will hereafter be referred to as 'the Application Site'.
- 1.1.4. The Application Site is currently greenfield agricultural land which is used as an orchard. A wooded Public Right of Way (PRoW) runs in a north-to-south direction and connects between Eastergate Lane and the B2233 Barnham Road. To the west of the Application Site is the current route for the A29. To the north of the Application Site is Eastergate Lane. There is a self-storage facility on the northern side of Eastergate Lane, opposite and residential dwellings on the south side of Eastergate Lane. The B2233 Barnham Road runs along the southern side of the Application Site. On the eastern side of the Application Site is a residential complex.

1.2 AIMS AND OBJECTIVES

- 1.2.1. WSP was commissioned by the Applicant to support the planning application with the implementation of an outline Ecological Management Plan (EMP) for inclusion within the Construction Environmental Management Plan (CEMP) (WSP 2020a). This document intends to:
- Provide an overview of the baseline ecological information for the Scheme and a surrounding area.
 - Provide a mitigation plan to be implemented during construction and operation, based on the recommendations of baseline ecological assessments and the Chapter 9 Ecology and Nature Conservation of the associated Environmental Statement (ES) (WSP 2020b).
- 1.2.2. The ecological mitigation strategy will enable compliance with relevant nature conservation legislation and planning policy and to avoid the killing/injury of notable and protected species.

1.3 LEGISLATION AND POLICY OVERVIEW

- 1.3.1. The outline EMP has been compiled with reference to the following relevant nature conservation legislation and planning policy, and the UK Biodiversity Framework from which the protection of sites, habitats and species is derived in England. The relevant legislation discussed within this report includes (detailed further within Appendix A):

National Legislation and Policy

- The Conservation of Habitats and Species Regulations 2017 (as amended) (Habitats Regulations);
- The Wildlife and Countryside Act 1981 (as amended) (WCA);

- Countryside Rights of Way Act 2000;
- The Natural Environment and Rural Communities (NERC) Act 2006 (England);
- The Protection of Badgers Act 1992;
- The Hedgerow Regulations 1997;
- The Wild Mammals (Protection) Act 1996;
- UK Government's 25 Year Environment Plan (DEFRA, 2018);
- The UK Post-2010 Biodiversity Framework (2011-2020) (JNCC and DEFRA, 2012);
- Biodiversity 2020: A strategy for England's wildlife and ecosystem services (DEFRA, 2011);
- UK Biodiversity Action Plan (UKBAP)¹; and
- The National Planning Policy Framework (NPPF) 2019 (Ministry of Housing Communities & Local Government, February 2019).

Local Policy

- West Sussex Transport Plan 2011 – 2026 (WSCC, 2011);
- West Sussex Structure Plan 2001-2016 (WSCC, 2005); and
- Adoption Arun Local Plan 2011-2031 (Arun District Council, 2018).

¹ The UK BAP has now been replaced by the UK Post-2010 Biodiversity Framework, however, it contains useful information on how to characterise important species assemblages and habitats which is still relevant.

2 ECOLOGICAL BACKGROUND

2.1 OVERVIEW

- 2.1.1. Habitats within the Application Site are considered to be of low to high ecological value including hedgerows, grasslands, woodland and scrub. Habitats of Principal Importance (HPI) were identified within the Application Site including traditional orchard and hedgerow.
- 2.1.2. Habitats within the Application Site and surrounding area are considered suitable to support a number of notable and protected species. After completion of specific ecological surveys, the following species/species groups are considered likely to be present to varying degrees within the Application Site; bats (foraging, commuting and roosting), badger *Meles meles*, other small mammals, wintering birds, breeding birds, common reptile species and invertebrates.

2.2 ECOLOGICAL RECEPTORS

- 2.2.1. The Scheme will result in a loss of habitat and disturbance to retained habitats within the “Survey Area” (defined within the A29 Preliminary Ecological Appraisal (PEA), WSP 2020c). In the absence of mitigation, habitat loss and disturbance could have negative effects on notable and protected habitats and species.
- 2.2.2. Table 2-1 provides details of the ecological receptors located within the Scheme and surrounding habitats. Information included within Table 2-1 is derived from the A29 Realignment PEA (WSP 2020c), bat report (WSP 2019a), badger report (WSP 2019b), hazel dormouse report (WSP 2019c), breeding bird report (WSP 2019d) wintering bird report (WSP 2019e), reptile report (WSP 2019f), great crested newt report (WSP 2019g) and invertebrate report (WSP 2019h), as well as the Habitat Regulations Screening Assessment (2019i).

Table 2-1 – Ecological Baseline

Ecological Receptor		Detail	Relevant Legislation and Policy
Designated Sites	Statutory Designated Sites	<p>No statutory designated sites were recorded within the Application Site.</p> <p>The Application Site was however found to be within 10km of five statutory sites of international importance (Habitats Sites), including Pagham Harbour Ramsar, Pagham Harbour Special Protection Area (SPA), Ducton to Bignor Escarpment Special Area of Conservation (SAC), Chichester to Langstone Harbours Ramsar and Solent and Dorset Coast Special Protection Area (SPA). Two additional SACs designated for bats were located within 30km, The Mens and Ebernoe Common.</p> <p>A Habitats Regulations Screening Assessment (HRSA) was undertaken for the Scheme. The HRSA concluded that the Scheme alone is not considered to have likely significant effects any of the five designated sites.</p> <p>No UK statutory designated sites are within 2km of the Scheme.</p>	<p>The Conservation of Habitats and Species Regulations 2017 (as amended) (“Habitats Regulations”) provide strict protection to sites of European and/or international importance. This includes requiring projects or plans to be screened for likely significant effects upon Special Protected Area (SPA), Special Area of Conservation (SAC) and candidate SACs (cSACs). Guidance also requires potential SPAs (pSPAs) and Ramsars are subject to the same assessment.</p>
	Non-Statutory Designated Sites	<p>No non-statutory designated sites were recorded within the Scheme.</p> <p>Non-statutory designated sites have been scoped out of the ES.</p>	
Habitats	Habitats (including HPI)	<p>The following HPI are present within 2km of the Application Site:</p> <ul style="list-style-type: none"> ■ Coastal and floodplain grazing marsh – two parcels 	<p>Semi-natural broadleaved woodland (deciduous woodland) and hedgerow are identified as HPI in accordance with Section 41 of the NERC Act 2006. Under Section 40 of this legislation, every public body (including</p>

Ecological Receptor	Detail	Relevant Legislation and Policy
	<ul style="list-style-type: none"> ■ Lowland meadows – two parcels ■ Lowland fens – one parcel ■ Deciduous woodland – 79 parcels ■ Traditional orchard – 12 parcels, some of which fall within the Scheme itself². <p>Within the Application Site itself, there are a number of habitats that qualify as HPI, including:</p> <ul style="list-style-type: none"> ■ Three species poor hedgerows, which from an ecological perspective are considered unlikely to meet the criteria for important hedgerows. ■ One parcel of plantation broadleaved woodland that is likely to qualify as Traditional orchard HPI. <p>Given the widespread nature of hedgerow HPI within the local area, it is considered to be of value at up to Local conservation value. Within the local area, traditional orchard occurs less frequency, with areas previously identified as traditional orchard HPI becoming scrubbed over that they no longer meet the criteria for HPI. As such, traditional orchard is considered to be of up to District conservation value.</p>	<p>planning authorities) must, 'in exercising its functions, have regard so far as is consistent with the proper exercise of those functions, to the purpose of conserving biodiversity'.</p> <p>At a local level, Policy CP7 Green Infrastructure Network of the core strategy states 'the integrity of the existing network of green infrastructure will be protected and enhanced through the lifetime of the Core Strategy. Planning permission for development that would harm the network will only be granted if it can incorporate measures that avoid the harm arising or sufficiently mitigate its effects.'</p>

² although the desk study shows several parcels of traditional orchard HPI falling within the Scheme, the Phase 1 habitat survey confirmed only one parcel present within the Scheme itself.

Ecological Receptor		Detail	Relevant Legislation and Policy
Protected and Notable Species	Bats (Foraging and Commuting)	<p>Habitats within the Application Site include orchard, semi-improved neutral grassland, scrub and hedgerows. Bat activity surveys focussed on linear features within the Application Site, such as hedgerows, with four static detectors deployed monthly between April and October.</p> <p>At least eight species of bat were recorded, however common and soprano pipistrelle <i>Pipistrellus pipistrellus</i> and <i>Pipistrellus pygmaeus</i> which are widespread and common bat species (BCT 2017a and 2017b) accounted for over 75% of all bat activity recorded. Ecobat analysis revealed these were the only two species that recorded high activity levels.</p> <p>The remaining recordings were made by a range of species, including greater horseshoe bat <i>Rhinolophus ferrumequinum</i>, barbastelle bat <i>Barbastella barbastellus</i> and Leisler's bat <i>Nyctalus leisleri</i>. Other species recorded included noctule <i>Nyctalus noctule</i>, serotine <i>Eptesicus serotinus</i> and Nathusius' pipistrelle <i>Pipistrellus nathusii</i>. Other genus were also recorded that could not be identified to species level including <i>Plecotus</i> sp. and <i>Myotis</i> sp.</p> <p>Location 3 alongside a row of hornbeam trees recorded the highest activity levels, with Location 2, alongside the footpath that bisects the Application Site is considered to be important for barbastelle bats.</p> <p>Overall, the Application Site is regarded to be conservation importance at up to a District level for its assemblage of bats.</p>	<p>All species of bats recorded within the UK are protected from killing, injury and disturbance and their roosts protected from damage or destruction under the Habitats Regulations. Protection is also afforded under the WCA with respect to disturbance of individuals occupying places of rest or shelter and obstruction of access to these. Activities that would otherwise constitute an offence under this legislation may be licensed by Natural England for certain purposes.</p> <p>Certain species of bats, including noctule bat <i>Nyctalus noctula</i>, brown long eared bat <i>Plecotus auritus</i> and soprano pipistrelle bat are also listed as Species of Principal Importance (SPI) for the conservation of biodiversity in England in accordance with Section 41 of the NERC 2006. Section 40 obliges public bodies (including local planning authorities) to have regard for the conservation of biodiversity (including SPI) when discharging their duties (including determining planning applications).</p>

Ecological Receptor	Detail	Relevant Legislation and Policy
	<p>Bats (Roosting)</p> <p>The PBRA identified a number of buildings / trees with the potential to support roosting bats:</p> <ul style="list-style-type: none"> ■ Three buildings with bat roosting potential, including one with low potential (B2) and two with moderate (B5 and B7). ■ Forty-four trees with bat roosting potential, including eight with low potential (T5, T7, T11-12, T14, T29, T31 and T43), 26 with moderate potential (T1, T4, T6, T8-10, T13, T15-16, T18, T21, T23-24, T27-28, T20, T32-33, T35-40, T42, T44), nine with high potential (T2, T17, T19, T20, T22, T25-26, T34, T41) and one confirmed bat roost (T3) (via the presence of droppings). <p>For the buildings, subsequent dusk emergence and dawn re-entry surveys were undertaken. During which, B5 was confirmed as a roost for soprano pipistrelle <i>Pipistrellus pygmaeus</i> and serotine <i>Eptesicus serotinus</i>. The likely absence of roosting bats was confirmed at buildings B2 and B7.</p> <p>For trees with moderate or high potential, at-height inspections were conducted, during which five trees were assessed as negligible (T3³, T15, T16, T33 and T41),</p>	

³ T3 was confirmed as a roost during the PBRA survey but was subsequently downgraded to negligible during the at-height surveys. This is due to branch damage that was sustained between the PBRA and at-height survey, exposing the features where the droppings had previously been recorded, and no longer provided the same protection and shelter for bats.

Ecological Receptor	Detail	Relevant Legislation and Policy
	<p>eight trees with low potential (T1, T6, T9, T13, T27, T32, T36 and T42), 18 trees with moderate potential (T2, T4, T8, T10, T18-19, T21-26, T30, T35, T37-38 and T40) and one confirmed roost (T20) (via the presence of droppings).</p> <p>One tree, T44 could not be climbed due to health and safety reasons. Instead, this tree was subject to a dusk emergence and dawn re-entry survey. The likely absence of roosting bats was confirmed during this survey.</p> <p>Overall, the Application Site is regarded to be conservation importance at up to a Local level for roosting bats.</p>	
Badger	<p>A badger survey, undertaken in April 2019, identified a number of setts within the Application Site and surrounding area, including a main sett located within the alignment of the Scheme. A second potential main sett was subsequently identified though an extension of the survey area.</p> <p>A badger bait marking survey was undertaken in September / October 2019 to identify whether multiple clans were present within the area.</p> <p>The results of the surveys identified one badger clan residing within the Badger Bait Marking Survey Area, with at the time of the survey, this clan had three very active setts (Sett 1-3) likely comprising a main, annex and subsidiary. Several outlier setts were also identified within the Application Site.</p> <p>Badgers are widespread within Sussex and southern England and are afforded legal protection for reasons of</p>	<p>The Protection of Badgers Act 1992 makes it illegal to wilfully kill, injure or take any badger, or attempt to do so. It also makes it an offence to intentionally or recklessly damage, destroy or obstruct access to any part of a badger sett.</p> <p>Activities that would otherwise constitute an offence under this legislation may be licensed by Natural England for certain purposes.</p>

Ecological Receptor	Detail	Relevant Legislation and Policy
	<p>animal cruelty, not rarity. However, given the presence of a main, annex, subsidiary and outlier setts, the Application Site and surrounding area is considered to be of Local importance for badgers.</p>	
Hazel Dormouse	<p>A hazel dormouse survey was undertaken during 2019. No evidence of this species was identified within the Application Site.</p> <p>As such, this species is considered likely absent from the Application Site.</p>	<p>Hazel dormice are protected from killing, injury and disturbance and their places of rest or shelter (occupied habitat) protected from damage or destruction under the Habitats Regulations. Protection is also afforded under the WCA with respect to disturbance of individuals occupying places of rest or shelter and obstruction of access to these. Activities that would otherwise constitute an offence under this legislation may be licensed by Natural England for certain purposes.</p> <p>Hazel dormice are also listed as SPI in accordance with Section 41 of the NERC Act 2006. Public bodies have an obligation under Section 40 to have regard for these species when carrying out their functions.</p>
Other Species of Principal Importance (SPI)	<p>As detailed in the PEA (Technical Appendix 9.1), records of other SPI were returned in the desk study, including hedgehog <i>Erinaceus europaeus</i> and polecat <i>Mustela putorius</i>, with suitable habitat for these species present within the Scheme. Further, although not identified within desk study records, the open grassland habitat has the potential to support brown hare <i>Lepus europaeus</i> and areas of hedgerow and unmanaged grassland have the potential to support harvest mice <i>Micromys minutus</i>. SPI are considered of importance at up to a Local level.</p>	<p>These species are listed as SPI in accordance with Section 41 of the NERC Act 2006. Public bodies have an obligation under Section 40 to have regard for these species when carrying out their functions.</p>

Ecological Receptor		Detail	Relevant Legislation and Policy
	Breeding Birds	<p>A total of 44 species were recorded during the breeding bird surveys, of these, 15⁴ are legally protected or species of conservation concern, including:</p> <ul style="list-style-type: none"> ■ three Wildlife and Countryside Act Schedule 1 species; ■ eight Species of Principal Importance (SPI) listed under the Natural Environment and Rural Communities (NERC) Act 2006; ■ six Birds of Conservation Concern (BoCC) red list species; and ■ seven BoCC amber species. <p>No specific barn owl surveys have been undertaken; however, a barn owl was recorded incidentally during a bat survey foraging within the Application Site and therefore may have a breeding site locally.</p> <p>Given the species records and the habitats present, the breeding bird community within the Application Site is considered to be of District conservation importance.</p>	<p>The Habitat Regulations 2017 Part 1 Regulation 10(2) & (3) state that local authorities ‘<i>must take such steps in the exercise of their functions as they consider appropriate to contribute to...the preservation, maintenance and re-establishment of a sufficient diversity and area of habitat for wild birds in the UK including by means of the upkeep, management and creation of such habitat...</i>’. The legislation continues to state that economic and recreation requirements must be taken into consideration in considering which measures are appropriate.</p> <p>Under the WCA all wild birds are protected from killing and injury, and their nests and eggs protected from taking, damage and destruction whilst in use. Additional protection is extended to species listed under Schedule 1 of the Act, meaning it is also an offence to disturb these species at or near the nest, or whilst they have dependent young.</p> <p>Some bird species are also listed as SPI in accordance with Section 41 of the NERC Act 2006. Public bodies have an obligation under Section 40 to have regard for these species when carrying out their functions.</p>
	Wintering Birds	<p>A total of 40 species were recorded during the wintering bird surveys, of these, 16⁴ are legally protected or species of conservation concern, including:</p> <ul style="list-style-type: none"> ■ three Wildlife and Countryside Act Schedule 1 species; 	

⁴ It should be noted that these categories are not exclusive, and a species can be listed in more than one conservation category (for example listed as both a SPI and BoCC red list species).

Ecological Receptor		Detail	Relevant Legislation and Policy
		<ul style="list-style-type: none"> ■ eight Species of Principal Importance (SPI) listed under the Natural Environment and Rural Communities (NERC) Act 2006; ■ eight Birds of Conservation Concern (BoCC) red list species; and ■ seven BoCC amber species. <p>No SPA qualifying species / assemblages (gulls) were recorded foraging in significant numbers, as such the wintering bird assemblage is considered to be of Local conservation importance.</p>	
	Reptiles	<p>The reptile survey confirmed the presence of two reptile species within the Application Site; slow worm <i>Anguis fragilis</i> and common lizard <i>Zootoca vivipara</i>, with low populations of both species present. Additionally, records of grass snake <i>Natrix helvetica</i> were returned in the desk study as within 150m of the Application Site. Due to the close proximity of these records and also the suitability of the habitats present on Application Site, it is considered that a low population of grass snake may also be present.</p> <p>Overall, the population of reptiles within the Survey Area is considered to be of importance at a Local level. This is because of widespread habitat within the local area and the low population size recorded of a relatively widespread species within West Sussex.</p>	<p>Native widespread reptile species (common or viviparous lizard, adder, grass snake and slow worm) are partially protected under Schedule 5 of the Wildlife and Countryside Act 1981 (as amended). This includes protection from killing and injury.</p> <p>All reptile species are also listed as SPI in accordance with Section 41 of the NERC Act 2006. Public bodies have an obligation under Section 40 to have regard for these species when carrying out their functions.</p>
	Amphibians (Great Crested Newt)	<p>A great crested newt (GCN) <i>Triturus cristatus</i>, Habitat Suitability Index (HSI) was undertaken within the Application Site and within 500m, during 2019. No</p>	<p>Great crested newts are protected from killing, injury and disturbance and their places of rest or shelter (occupied habitat) protected from damage or destruction under the Habitats Regulations. Protection is also afforded under the</p>

Ecological Receptor	Detail	Relevant Legislation and Policy
	<p>waterbodies were identified which were considered suitable to support GCN within the Application Site.</p> <p>As such, GCN species is considered likely absent from the Application Site.</p>	<p>Wildlife and Countryside Act 1981 (as amended) with respect to disturbance of individuals occupying places of rest or shelter and obstruction of access to these. Activities that would otherwise constitute an offence under this legislation may be licensed by Natural England for certain purposes.</p> <p>Great crested newts and common toad are also listed as SPI in accordance with Section 41 of the NERC Act 2006. Public bodies have an obligation under Section 40 to have regard for these species when carrying out their functions.</p>
Terrestrial Invertebrates	<p>Due to the presence of orchard habitat within the Application Site, invertebrate surveys were undertaken, with a particular focus on noble chafer <i>Gnorimus nobilis</i> found in traditional orchards. During the surveys, noble chafer were not identified so their likely absence from the Application Site is assumed.</p> <p>The surveys recorded six species of conservation concern including:</p> <ul style="list-style-type: none"> ■ three nationally scarce species (an ant <i>Lasius brunneus</i>, longhorn beetle <i>Prionus coriarius</i> and flower beetle <i>Mordellistena humeralis</i>); ■ three SPI (small heath butterfly <i>Coenonympha pamphilus</i>, ghost moth <i>Hepialus humuli</i> and cinnabar moth <i>Tyria jacobaea</i>). <p>Additionally, stag beetle <i>Lucanus cervus</i> a SPI which are of high conservation concern were recorded incidentally on Application Site, with suitable habitat present, and are considered of importance at up to a Local level.</p>	<p>Some invertebrate species (including stag beetle) are listed as SPI in accordance with Section 41 of the NERC Act 2006. Public bodies have an obligation under Section 40 to have regard for these species when carrying out their functions.</p> <p>Stag beetle are also protected under Schedule 5 of the Wildlife and Countryside Act.</p>

3 ECOLOGICAL MANAGEMENT PLAN

3.1 OVERVIEW

- 3.1.1. Ecological mitigation measures are required to avoid and reduce potential effects that could occur during the operation and construction phases of the Scheme. The Scheme will integrate a landscape strategy to mitigate effects upon protected species and achieve 10% Biodiversity Net Gain (BNG), a drainage strategy that promotes habitat diversity and a lighting strategy that is sensitive to ecological features such as foraging and commuting bats.
- 3.1.2. Further measures are also outlined to ensure the protection of retained habitats, protection of notable species and avoidance of habitat degradation during the construction phase.
- 3.1.3. Figure 3 provides indicative locations for ecological mitigation measures including bat boxes, bird boxes and refugia piles.

3.2 DESIGN MEASURES

AVOIDANCE MEASURES

- 3.2.1. The Scheme designs will ensure retention and protection of woodland and hedgerows as far as possible in order to minimise effects upon a range of protected species (bats, badgers, other mammals, breeding birds, reptiles, and invertebrates). This includes retention and maintenance of HPI (woodland, hedgerows and waterbody) for their intrinsic value.
- 3.2.2. Where habitat loss is unavoidable, compensation will be required in line with local and national policy as discussed below in the landscape strategy.

LANDSCAPE STRATEGY

- 3.2.3. To compensate for the loss of habitat during construction of the Scheme, a strategic landscape strategy has been designed, as detailed within Chapter 10 of the ES, Landscape and Visual Assessment (WSP 2020d). The layout of habitats is shown in the landscape general arrangement plans (shown in Figure 2 - Drawing ref A29-WSP-LA-GA-005).
- 3.2.4. The landscape strategy creates new habitat and enhances habitats within the Scheme to provide greater opportunities for protected and notable species such as bats, badger, birds, amphibians and invertebrates. The key features of the proposed landscape mitigation include:
- New woodland planting to provide green visual containment in addition to creating habitat for wildlife.
 - New specimen tree planting to enhance visual appeal and integrate the Scheme into the surrounding landscape.
 - New hedgerow planting to enhance visual amenity of the Scheme, respond positively to the local character and screen the nearby residents from the proposed noise barrier.
 - Areas of wildflower grassland and bulb planting to enhance the biodiversity along with visual appeal.
 - Established areas of existing vegetation are proposed to be retained and enhanced where possible.
- 3.2.5. The landscape strategy proposes to create eight habitat types, broadly categorised as below:

- shrub;
- scattered specimen trees;
- woodland core;
- woodland edge planting;
- native hedgerow;
- species-rich grassland; and
- species-rich wet grassland.

- 3.2.6. These habitats will provide suitable foraging opportunities for a variety of species including bats, terrestrial mammals (such as badger), birds, reptiles, common amphibians and invertebrates. Woodland and scrub creation will provide nesting opportunities for birds as well as refuge for mammals, amphibians and invertebrates.
- 3.2.7. The landscape strategy should utilise a native and species-rich mix of plants for all habitat types, mirroring surrounding retained semi-natural habitats including species-rich grassland and broadleaved woodland. Utilising native species, flowering species and berry bearing shrubs will benefit a range of wildlife, providing food source throughout the year.
- 3.2.8. In line with local and national policy, the Scheme aims to achieve at least a 10% gain in biodiversity post-development, as supported by a BNG assessment (WSP 2020e). The final figures and results of the assessment are detailed in the BNG report, however it is understood that a net gain in biodiversity of at least 10% has been reached.

Landscape Management/Maintenance

- 3.2.9. Specific detail of habitat management (e.g. grassland mowing regime etc.) is provided in the Landscape Maintenance and Management Plan (LMMP) (WSP 2020f). Appropriate landscape planting recommendations are provided within the LMMP to ensure:
- correct planting/sowing seasons;
 - correct soil conditions are created for specific species/habitats;
 - sufficient spacing is provided between standard trees to prevent future oversharing; and
 - viability of trees, bulbs and grassland mixes.
- 3.2.10. New and retained landscaped areas should be subject to low-intensity management regimes. This should include:
- Sensitively timed grass cutting, as to avoid the peak flowering season and retain a species-rich sward.
 - Grass cuttings/arising should be left in situ for a few days to drop seeds as appropriate, prior to removal. Arisings should be removed to prevent an increase in soil fertility and retain the species-rich grasslands.
 - No more than one cut/prune of hedgerow and standard trees per year. This should also be undertaken only once specimens have fruited in order to maximise food availability for a range of wildlife.

LIGHTING STRATEGY

- 3.2.11. Artificial lighting may affect sensitive fauna within the Scheme, most notably bat species. Lighting can affect bat roosts, commuting routes and established and created dark corridors. The lighting strategy for the Scheme should therefore be developed to be sensitive to bats. A bat sensitive

lighting strategy will also reduce the effect of lighting upon other light sensitive and nocturnal species, such as badger, crepuscular birds and invertebrates.

- 3.2.12. Bat activity surveys within the Application Site identified Folly Foot Farm Barn, Land to south of Eastergate Lane and the PRow (Footpath 318) as being sensitive areas for bat species.
- 3.2.13. In accordance with best practice guidance (Institution of Lighting Professionals (IPL) (2018)), the lighting strategy (WSP 2020g) aims to:
- Avoid light spill onto confirmed or suspected roosts, in addition to new bat boxes, primarily through good design and secondarily by physical shields, where necessary.
 - Avoid, light spill onto trees and hedgerows, minimised through good design, with physical shields installed where necessary, and maintain dark corridors along retained areas of retained woodland and hedgerows, to ensure continued connectivity, notably along the PRow (Footpath 318). A 15m buffer will be utilised along the PRow in which there will be no lighting.
 - Creation of a 'buffer zone' of very low illuminance (if any) adjacent to established or proposed key habitats, such as adjacent to treelines.
 - Landscaping measures in the form of shrubs and tree planting to further act as secondary mitigation to screen and soften the effects of installed artificial light sources should be considered.
 - Use the minimum light levels necessary for the relevant task / function, this may equate to reducing light intensity, and/or using the minimum number of light sources or minimum column height.
 - Use hoods, louvres or other luminaire design features to avoid light spill onto retained and newly created areas of vegetation likely to be used by foraging and commuting bats. In particular, light spill on to any trees with bat roost potential from the construction or operational phase lighting should be avoided to minimise the risk of disturbance.
 - Use narrow spectrum light sources where possible to lower the range of species affected by lighting, specifically avoiding shorter wavelength blue light, using instead warm/neutral colour temperature lighting.
 - Use light sources that emit minimal ultra-violet light to avoid attracting night-flying invertebrate species which in turn may attract bats to the light.
- 3.2.14. It is understood that the lighting strategy will utilise Mayflower smart control lighting, a control that makes it is possible to establish a site-specific switching regime, whereby each lighting unit fitted with a Mayflower external node can be controlled individually and set to dim at any time of day during operation. Furthermore, the dimming regime can be adjusted at any time to suit seasons. By using this control, it will be possible to reduce the lighting at the times when bats are active.

DRAINAGE STRATEGY

- 3.2.15. A sensitive drainage strategy will be implemented for the operation of the Scheme. Details of the drainage strategy are set out within Chapter 11 Water Resources and Flood Risk of the ES (WSP 2020h), the Flood Risk Assessment (FRA) (WSP 2020i) and the Surface Water Drainage Strategy (SWDS) (Capita 2020).
- 3.2.16. A combination of Sustainable Drainage Systems (SuDS) features will be designed into the Scheme to provide mitigation for the potential effect of increases in physical contamination (i.e. sedimentation) of surface water bodies. Whilst the drainage strategies will primarily aim to mitigate the potential impacts upon groundwater and surface water, a number of these features will also

create valuable wetland habitats for notable and protected species. These features will include swales and lined attenuation ponds for the eastern portion of the Scheme.

- 3.2.17. The SuDS features should be appropriately enhanced to increase their ecological value and subsequently benefit wildlife. Section 3.4 provides enhancement measures for SuDS features.

SPECIES-SPECIFIC MITIGATION

Bat Foraging and Commuting

- 3.2.18. An appropriate lighting strategy will be created for the Application Site as discussed above. In particular, the lighting strategy will require that new permanent lighting is the minimum required and will avoid light spill directly onto retained and newly created ecological features (e.g. hedgerows and woodland) within the Scheme.

- 3.2.19. Bat activity surveys within the Application Site the PRoW (Footpath 318) as being sensitive areas for rare bat species, including barbastelle bat. As such, no lighting will be placed within a 15m buffer of the PRoW.

Bat Roosting

- 3.2.20. To mitigate for the loss of roosting opportunities across the Application Site, and to enable future monitoring, new roosting opportunities in the form of bat boxes will be installed on retained mature trees in suitable locations, either within the Application Site itself, or within nearby land under the ownership of WSCC.
- 3.2.21. The number of bat boxes installed will at least replicate the number of Potential Roost Features (PRFs) lost from the six moderate/high potential trees (12 PRFs in total), with another five additional PRFs provided as an enhancement measure. Bat boxes should be targeted towards species likely to use the Survey Area, namely tree/woodland dwelling species such as common pipistrelle or noctule. Indicative designs to be included in the mitigation include:
- 2F Schwegler Bat Box – for general purpose;
 - 2FN Schwegler Bat Box – suited to noctule roosting requirements;
 - 1FF Schwegler Bat Box – for general purpose and maternity colonies; and
 - 1FW Bat Hibernation Box – for hibernation.
- 3.2.22. Bat boxes should be installed on mature trees at approximately 4 metres above the ground and placed in a range of locations at slightly different heights and facing in slightly different directions to give a choice of roost site options (Mitchell-Jones, 2004). The direction of the boxes should be selected to avoid facing them into the prevailing weather and will preferably be positioned facing in a southerly direction (i.e. south-west through south to south-east) where they will receive a good degree of sunlight. Bat boxes should be installed in positions where they are out of reach of people from the ground and high enough to deter cats and other predators.
- 3.2.23. Recommended locations for bat box installation include retained orchard and woodland habitat within habitat immediately south of the west of the Application Site as well as along the retained and dark corridor of the PRoW (Footpath 318).

Badger

- 3.2.24. As the use of the Application Site by badgers will likely change over time, with some setts likely to become inactive and new setts likely to be created, a walkover survey will be undertaken prior to commencement of works, and the licence application being submitted.
- 3.2.25. It will be necessary to close the setts under a licence from Natural England. These licences are typically only issued for activities affecting setts to occur between 1st July and 30th November inclusive, in order to avoid the badger breeding season. A suitable mitigation strategy will need to be in place to obtain the licence and is likely to include the installation of one-way badger gates, kept in place for a minimum of 21 days, monitoring of the sett for signs of badgers entering or leaving the sett and destruction of the sett once badgers are excluded to reduce the risk of badgers re-occupying the sett. The area will also be secured against re-entry by badgers by using heavy-gauge chain link fencing.
- 3.2.26. As one of the setts to be lost is a main sett, it will be necessary to install an artificial sett, which will need to be proven to have been occupied by badgers, prior to the closure of their main sett. A preliminary design has been discussed with Natural England through the discretionary advice service, with final design to be refined during the application of the Natural England sett closure licence. This artificial sett is currently scheduled for construction later in 2020 and should be installed at least six months prior to sett closure.
- 3.2.27. Permanent badger fencing will be installed either side of the new road, with an underpass located to the west of the Scheme, close to the current main sett to allow badgers to forage on either side of the road and therefore reducing the risk of vehicle collision. The fencing design will be refined during the application for the sett closure licence, however will be dug deep to prevent badgers tunnelling underneath and also designed to persuade badgers to utilise the underpass.

Birds

- 3.2.28. To mitigate for the loss of nesting opportunities across the Application Site, at least six bird boxes will be installed in suitable locations within retained habitat.
- 3.2.29. Bird boxes designs should reflect the nesting requirements for species known to use the Scheme and that are local conservation priorities such as house sparrow *Passer domesticus* and starling *Sturnus vulgaris*, as well as common and widespread woodland species. Box dimensions and placement should be tailored to the target species. Indicative designs to be included in the mitigation include:
- 1B Schwegler Nest Box – cavity nest box;
 - 2H Schwegler Robin Box – open fronted box;
 - CedarPlus Triple Sparrow House– for sparrow species; and
 - 3S Schwegler Starling Nest Box– for use by starling and other cavity nesters.
- 3.2.30. In general, boxes should be installed on mature trees 2-4m high and placed to avoid strong sunlight and the wettest winds (usually north to east, depending on the shade level), and the entrance should face slightly downwards to protect from the rain. Boxes should have a clear flight path on the approach and be relatively undisturbed.
- 3.2.31. Indicatively the boxes should be placed within retained woodland and orchard habitat to the south of the Application Site, or within the retained PRow (Footpath 318).

Reptiles

- 3.2.32. To mitigate for the loss of reptile refuge across the Application Site, at least six refugia/hibernacula will be installed in suitable locations within retained habitat.
- 3.2.33. Refugia piles should be installed within retained grasslands on the edge of scrub habitat. They should be built in line with the Reptile Habitat Management Handbook (Edgar, Foster and Baker 2010), and include brush and log piles to create cover, provide additional structure to existing habitat and enhance prey availability.
- 3.2.34. It is recommended that at least one of the refugia piles also functions as a hibernacula. This hibernacula should also be built in line with the Reptile Habitat Management Handbook (Edgar, Foster and Baker 2010), to provide hibernation opportunities throughout the winter season.

Invertebrates

- 3.2.35. Dead wood will be retained within woodland habitats where possible to mitigate for the loss of suitable stag beetle habitat. The deadwood should be retained in line with Buglife guidance (Buglife 2011), by leaving standing deadwood in situ, creating log piles and leaving fallen deadwood on the ground.
- 3.2.36. Log piles created as reptile refugia will also serve as invertebrate habitat. These should be placed in grassland and scrub habitats, within sunny positions to benefit invertebrate species.

3.3 CONSTRUCTION MEASURES

- 3.3.1. The following measures are recommended during the construction phase of the Scheme to ensure the avoidance and reduction of killing/injury of notable and protected species as well as the protection of retained habitats. This section should be read alongside the CEMP.

GENERAL CONSTRUCTION MEASURES

- 3.3.2. General environmental protection measures must be implemented during the construction phase of the Scheme as included within the CEMP. Such measures include best environmental practice guidance outlined in the Government's Pollution prevention for businesses (DEFRA, 2019) and those outlined by the Construction Industry Research and Information Association guidance (CIRIA, 2015). The following minimum standards must be adhered to prevent negative ecological effects beyond the Scheme boundary:
- Measures must be taken to prevent dust and other emissions from construction affecting the retained habitats and land beyond the Scheme.
 - Chemicals and fuels must be stored in secure containers located away from watercourses or water bodies. Spill kits must be available.
 - Implementation of a construction-phase drainage strategy to intercept, capture and attenuate surface water runoff.
 - Excavations must be covered or securely fenced (with no potential access points beneath fencing) when the construction site is closed (e.g. overnight) to prevent entrapment of animals, specifically badgers.
 - Retained trees and hedgerow must be protected in accordance with British Standard BS5837:2012 Trees in Relation to Construction, including the erection of robust protective fencing encompassing root protection areas.

- Noise and vibration must be controlled and kept to the minimum necessary, especially with regard to working in close proximity to known active badger setts.
- Lighting used for construction must be kept to a minimum and switched-off when not in use.
- Lighting should be positioned so as not to spill on to adjacent land or retained vegetation within the Scheme.
- Night works should be avoided where possible to reduce lighting of sensitive habitats and disturbance to species.

SPECIES SPECIFIC CONSTRUCTION MEASURES

Badger

- 3.3.3. Badgers use the wider area for foraging and commuting purposes and therefore measures need to be put in place during the construction phase to minimise effects upon badger movement and foraging activity. These will include measures such as:
- fencing dangerous areas of the construction site (e.g. deep excavations) or providing a means of egress from shallow excavations;
 - avoidance of storage of plant and materials on areas of potential foraging habitat (e.g. retained grassland);
 - noise reduction measures during construction;
 - avoidance of night works, unless specifically required, to avoid disturbance by artificial lighting; and
 - where required use of lighting hoods, cowls or shields to avoid light spill onto setts or badger paths.
- 3.3.4. For setts that are located outside the Scheme extent, to ensure they are not affected by the works, a 30m buffer around each sett in which no construction activities can take place will be clearly marked.

Bats

- 3.3.5. All retained trees will be protected in accordance with British Standard BS5837:2012 Trees in Relation to Construction, including the erection of robust protective fencing encompassing root protection areas.
- 3.3.6. To avoid disturbance to retained trees and buildings with suitability to support roosting bats, the CEMP will include best practice construction measures to minimise the effects of noise pollution, dust and air pollution and visual intrusion during construction, as above.
- 3.3.7. Lighting during the construction phase will be kept to a minimum to avoid light spillage on retained habitat that bats will use for foraging and commuting purposes, in line with the measures outlined above.
- 3.3.8. Prior to tree removal, as bats may use PRFs on a transient basis and there will be at least a 12-month time lapse between the most recent surveys (2019) and construction commencing, an updated ground level inspection will be completed to confirm the level of potential for bat roosts to be present. This is to ensure that mitigation is appropriate and based on information current at the time of works. The following approach will then be taken:
- Trees assessed as having low potential to support bat roosts will be soft-felled by suitably qualified arborists, following an at-height inspection of any potential roost features to confirm the absence of roosting bats (and evidence of roosting bats). Contractors with basic bat awareness

should be employed and guidance within British Standard BS8596:2015 Surveying for Bats in Trees and Woodland should be adhered to. In addition, where it is not possible to thoroughly assess PRFs, sectional soft felling methods should be used to remove those features. This involves lowering the whole section of branch with the PRF to the ground, not cross-cutting or fracturing it. The PRF section should then be placed in a suitable location (e.g. within retained woodland) and should be left overnight, with the PRF facing upwards, with free routes of dispersal, for any bats to disperse naturally. As the trees are not likely to offer hibernation potential to bats, felling works should be undertaken in the winter (November – March depending on weather conditions) where possible, when bats can reasonably be assumed to be absent.

- Trees assessed as having moderate or high potential to support bat roosts will be subject to a climbing inspection to enable a thorough assessment of potential and to search for evidence indicating the presence of roosting bats. If at this stage the potential is downgraded to low, the trees will be soft felled by suitably qualified arborists as above.
- In the event that the presence of a bat roost is highlighted at this stage, the requirement for works affecting the roost would be reconsidered to identify whether adverse effects can be avoided. Where possible, in this scenario proposals would be updated to enable retention and protection of the bat roost. In the event that retention is not possible, a licence would be sought from Natural England to permit works to proceed, the licence application would be subject to a detailed method statement.

3.3.9. If it is not possible to avoid disturbance effects to Building B5 via careful timing of works, then it may be necessary to obtain a licence from Natural England to permit works to proceed, which would be subject to a detailed method statement. As Building B5 has been assessed as having negligible potential to support hibernating bats, avoidance of impacts would include timing the works to take place between November – February (weather dependent) when bats are likely absent from the roost.

3.3.10. In the unlikely event that any bats are encountered or PRF's of moderate/ high suitability for supporting roosting bats are identified during the construction phase, felling works should cease and further professional ecological advice should be sought.

Birds

3.3.11. Suitable bird nesting habitat clearance should be undertaken outside of the bird nesting season (indicatively March to September). Where clearance of habitat is not possible outside of the breeding bird season, all areas to be affected will be checked for evidence of nesting birds by an ecologist. The check will be undertaken a maximum of 24 hours prior to the vegetation removal taking place.

3.3.12. If any active bird nests are discovered these will be cordoned off with a buffer of at least 5m (this may increase depending on species, proposed works and location) where no potentially disturbing works will take place. The buffer will remain in place until the young have fledged and the nest vacated. Upon fledging, a second nesting bird check would then be undertaken to ensure the vegetation does not contain any further active nests prior to felling or removal works taking place.

Small Mammals, Reptiles and Amphibians

3.3.13. Should the removal of any rubble, brash or log piles be required as part of the Scheme then a precautionary methods of work (PMoW) should be employed. This is to ensure compliance with

legislation and planning policy regarding small mammals (including hedgehog), common reptile species and amphibian species listed as NERC priority species.

- 3.3.14. It is advised that all areas of suitable habitat will be treated as potentially supporting reptiles. In all areas of suitable habitat, mitigation will entail the clearance of vegetation outside of the sensitive hibernation season (indicatively November-February inclusive, but weather dependent). Where tall herbaceous vegetation is cleared during the active season for reptiles, then it will be undertaken in two stages over at least two consecutive days and include an initial cut down to 150mm, with the second cut reducing vegetation as close as possible down to ground level in order to progressively render habitat unsuitable for reptiles. Any refugia will be dismantled by hand with all works undertaken under the supervision of a suitably qualified ecologist to minimise the risk of killing or injury to reptiles. Works will be temporarily halted if individual animals are encountered to allow the animal to disperse from the work site.

3.4 ECOLOGICAL ENHANCEMENT

HABITAT CREATION

- 3.4.1. In accordance with national and local planning policy, the Scheme should aim to enhance retained habitats. The landscape strategy will ensure that a variety of habitats will be created including for a diverse species mix. In addition to this the following measures should be considered:
- Inclusion of nectar-rich plant species in soft landscaping areas that are attractive to night-flying insects to enhance foraging opportunities for bats (BCT 2015). For example, these could include oxeye daisy *Leucanthemum vulgare*, knapweed *Centaurea nigra*, primrose *Primula vulgaris*, common mallow *Malva neglecta*, wild marjoram *Origanum vulgare* and wild thyme *Thymus polytrichus*.
 - Creation of refugia/hibernacula - habitat, brash or rubble piles installed in landscaped areas in order to provide refuge and hibernation opportunities small mammals such as hedgehog.
 - Purpose built invertebrate “hotels” could be installed in landscaped areas to provide refuge for specific taxonomic groups, i.e. provision of nesting boxes for solitary bees.
 - Standing water to be incorporated within the SuDs features should provide a permanent source of water for species such as badger, hedgehog, birds, amphibians and invertebrates, where drainage conditions allow. This should incorporate varying depths and slopes within the standing water to provide varying water depths and conditions. A suitable planting regime should also be used, comprising a native species rich mix of submerged, emergent and marginal vegetation to promote aquatic floristic diversity. The swales/ species-rich wet grassland should be planted with an appropriate mix of native marshy grassland species.

4 CONCLUSION

- 4.1.1. This mitigation strategy provides a summary of the ecological baseline for the Scheme. As supported by ecological survey and desk study data, the habitats within the Scheme are considered suitable to support:
- bats (foraging, commuting and roosting);
 - badgers;
 - other small mammals;
 - wintering birds;
 - breeding birds;
 - reptiles; and
 - invertebrates.
- 4.1.2. Ecological mitigation measures required to fulfil legislation and local/national planning policy are outlined. These include:
- a detailed landscape strategy that promotes habitat diversity and with the aim to achieve 10% Biodiversity Net Gain (BNG);
 - a drainage strategy that promotes habitat diversity;
 - a lighting strategy sensitive to ecological features such as foraging and commuting bats;
 - further ecological enhancement measures including bird boxes, bat boxes and habitat features for small mammals, amphibians and invertebrates; and
 - construction measures to avoid the damage/disturbance to notable habitats and killing/injury of notable and protected species.

5 REFERENCES

PROJECT REFERENCES

- WSP (2019a). A29 Realignment. Bat Report.
- WSP (2019b). A29 Realignment. Badger Report.
- WSP (2019c). A29 Realignment. Hazel Dormouse Report.
- WSP (2019d). A29 Realignment. Breeding Bird Report.
- WSP (2019e). A29 Realignment. Wintering Bird Report.
- WSP (2019f). A29 Realignment. Reptile Report.
- WSP (2019g). A29 Realignment. Great Crested Newt Report.
- WSP (2019h). A29 Realignment. Invertebrate Report.
- WSP (2019i). A29 Realignment. Habitat Regulations Screening Assessment.
- Capita (2020). Surface Water Drainage Strategy (SWDS).
- WSP (2020a). A29 Realignment. Construction Environmental Management Plan.
- WSP (2020b). A29 Realignment. Environmental Statement.
- WSP (2020c). A29 Realignment. Preliminary Ecological Appraisal Report.
- WSP (2020d). A29 Realignment. Environmental Statement. Chapter 10 Landscape and Visual.
- WSP (2020e). A29 Realignment. Biodiversity Net Gain Assessment.
- WSP (2020f). A29 Realignment Landscape Maintenance and Management Plan.
- WSP (2020g). A29 Realignment. Lighting Assessment Report.
- WSP (2020h). A29 Realignment. Environmental Statement. Chapter 11 Water Resources and Flood Risk.
- WSP (2020i). A29 Realignment. Flood Risk Assessment.

TECHNICAL REFERENCES

- Arun District Council (2018). Adoption Arun Local Plan 2011-2031
- Bat Conservation Trust (BCT) (2015). Encouraging bats. A guide for bat-friendly gardening and living.
- Bat Conservation Trust (2017a). National Bat Monitoring Programme Population Trends | The state of the UK's bats 2017.
- Bat Conservation Trust (2017b). National Bat Monitoring. Annual report 2017.
- British Standards Institution (2012). BS 5837:2012 Trees in relation to design, demolition and construction – Recommendations. BSI, London.
- BSI (2013). Biodiversity code of practice for planning and development: BS42020. BSI. London.
- Buglife (2011). Scottish Invertebrate Habitat Management: Deadwood. Buglife – The Invertebrate Conservation Trust.
- CIEEM (2019). Guidelines for Ecological Impact Assessment in the UK and Ireland: Terrestrial, Freshwater, Coastal and Marine.
- CIEEM, CIRIA & IEMA. (2016). Biodiversity Net Gain: Good practice principles for development.
- Collins J. (ed.) (2016). Bat Surveys for Professional Ecologists, Good Practice Guidelines (3rd Edition). The Bat Conservation Trust, London.
- Department for Environment, Food and Rural Affairs (2011). A strategy for England's wildlife and ecosystem services. DEFRA, London.
- Edgar, P., Foster, J. and Baker, J. (2010). Reptile Habitat Management Handbook. Amphibian and Reptile Conservation, Bournemouth.

- HMSO (Her Majesty's Stationary Office) (1981). Wildlife and Countryside Act (as amended by the Countryside and Rights of Way Act 2000). HMSO, Norwich.
- HMSO (1992). The Protection of Badgers Act. (The Badgers Act), HMSO, London.
- HMSO (1996). The Wild Mammals (Protection) Act. HMSO, London.
- HMSO (1997). The Hedgerows Regulations, SI 1997/1160. HMSO, London.
- HMSO (2006). Natural Environment and Rural Communities Act. HMSO, Norwich.
- HMSO (2017). The Conservation of Habitats and Species Regulations 2017 as amended (the Habitat Regulations), HMSO, Norwich.
- Institution of Lighting Professionals (IPL) (2018). Guidance Note 8 Bats and artificial lighting.
- JNCC Biodiversity Reporting and Information Group (2008). UK Biodiversity Action Plan
- JNCC and DEFRA (2012). UK Post 2010 Biodiversity Framework. Available online: <http://jncc.defra.gov.uk/page-6189>. [Accessed July 2014].
- Ministry of Housing, Communities and Local Government (2019). The National Planning Policy Framework.
- Natural England (2019). The Biodiversity Metric 2.0. Available:<http://publications.naturalengland.org.uk/publication/5850908674228224> [Accessed August 2020].
- Office of the Deputy Prime Minister (ODPM) (2005). Government Circular: Biodiversity and Geological Conservation – Statutory Obligations and their Impacts within the Planning System.
- West Sussex County Council (2011). West Sussex Transport Plan 2011-2026
- West Sussex County Council (2005). West Sussex Transport Plan 2001-2016

6 FIGURES


Figure 1 –Scheme Location Plan

Figure 2 – Landscape Plan (A29-WSP-LA-GA-005)

Figure 3 – Indicative Ecological Mitigation



THIS DRAWING MAY BE USED ONLY FOR THE PURPOSE INTENDED AND ONLY WRITTEN DIMENSIONS SHALL BE USED

 Red Line Boundary

Copyright
 This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office.
 © Crown copyright
 Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings.
 © Crown copyright and database right 2020

Revision Details	By	Date	Suffix


Drawing Status: **FINAL**

Job Title: **A29 Phase 1 Planning Application**

Drawing Title: **Scheme Location Plan**


Scale at A3

Drawn	UKBDW001		
Stage 1 check	AS	Stage 2 check	DY
		Originated	DY
		Date	25/08/2020



Drawing Number

Path: \\uk.wspgroup.com\central\data\Projects\2020\60779 - WSCC - A29 Phase 1 Planning Application\03 WSP\GIS\locScheme_LocationPlan.mxd



DO NOT SCALE

- NOTES:
1. ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
 2. DO NOT SCALE, IF IN DOUBT CONTACT WSP PROJECT MANAGER.
 3. THE WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE DFT MCHW, DMRB AND THE LOCAL REQUIREMENTS OF WEST SUSSEX COUNTY COUNCIL DESIGN GUIDE & SPECIFICATIONS.
 4. INDICATIVE LOCATIONS OF ARBORICULTURAL, ECOLOGICAL AND ACOUSTIC ELEMENTS.

KEY:

	Extent of works
	Extent of temporary land take
	Temporary use land
	Existing Vegetation
	Specimen Tree
	Shrub
	Woodland Edge
	Woodland Core
	Amenity Grass Mix
	Wildflower Meadow Grass Mix
	Wetland Grass Mix
	Areas to retain maximum feasible amount of existing vegetation where possible
	Root Protection Area - indicative location only
	Tree Preservation Order - indicative location only

REV	DATE	BY	DESCRIPTION	CHK	APP
G	02/10/2020	GG	UPDATE TO LATEST HIGHWAYS LAYOUT & REDLINE BOUNDARY	LG	KM
F	20/08/2020	GG	UPDATE IN LINE WITH NEW POND AND HIGHWAYS LAYOUTS AND REDUCED WILDFLOWER MEADOW	LG	KM
E	06/08/2020	GG	UPDATE TO NEW DRAINAGE LAYOUT	LG	KM
D	21/07/2020	GG	UPDATE TO HEDGE MAINTENANCE REQUIREMENTS	LG	KM
C	20/07/2020	GG	UPDATE TO ORCHARD MAINTENANCE REQUIREMENTS/WOODLAND	LG	KM
B	01/07/2020	GG	UPDATE TO POND LAYOUTS/SOUND BARRIER	LG	KM
A	01/05/2020	GG	FIRST ISSUE	LG	KM

DRAWING STATUS: S2 - FOR INFORMATION

wsp

3rd Floor, Kings Orchard, 1 Queen St, Bristol, BS2 0HQ, UK
T+ 44 (0) 1179 306 200
wsp.com

CLIENT: WSCC

ARCHITECT: -

SITE/PROJECT: A29

TITLE: SOFT LANDSCAPE PLAN SHEET 1 OF 5

SCALE @ A1: 1:500	CHECKED: LG	APPROVED: KM
PROJECT NO: 70060779	DESIGNED: GG	DRAWN: GG
		DATE: October 20

DRAWING No: A29-WSP-LA-GA-001

© WSP UK Ltd

File: A29-WSP-LA-GA-001-01.dwg
 Project: A29-WSP-LA-GA-001
 Date: 02/10/2020 10:42:40
 Author: G. Cohen
 Reproduced from the Ordnance Survey map with the permission of the Controller of Her Majesty's Stationary Office. Licence no. 100048755. Crown copyright reserved.



DO NOT SCALE

- NOTES:
1. ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
 2. DO NOT SCALE, IF IN DOUBT CONTACT WSP PROJECT MANAGER.
 3. THE WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE DFT MCHW, DMRB AND THE LOCAL REQUIREMENTS OF WEST SUSSEX COUNTY COUNCIL DESIGN GUIDE & SPECIFICATIONS.
 4. INDICATIVE LOCATIONS OF ARBORICULTURAL, ECOLOGICAL AND ACOUSTIC ELEMENTS.

KEY:

	Extent of works
	Extent of temporary land take
	Temporary use land
	Existing Vegetation
	Hedge
	Specimen Tree
	Shrub
	Woodland Edge
	Woodland Core
	Amenity Grass Mix
	Wildflower Meadow Grass Mix
	Wetland Grass Mix
	Areas to retain maximum feasible amount of existing vegetation where possible
	Root Protection Area - indicative location only
	Tree Preservation Order - indicative location only
	Proposed Bench

Proposed artificial badger sett location

REFER TO SHEET 1

REFER TO SHEET 3

REV	DATE	BY	DESCRIPTION	CHK	APP
G	02/10/2020	GG	UPDATE TO LATEST HIGHWAYS LAYOUT & REDLINE BOUNDARY	LG	KM
F	20/08/2020	GG	UPDATE IN LINE WITH NEW POND AND HIGHWAYS LAYOUTS AND REDUCED WILDFLOWER MEADOW	LG	KM
E	06/08/2020	GG	UPDATE TO NEW DRAINAGE LAYOUT	LG	KM
D	21/07/2020	GG	UPDATE TO HEDGE MAINTENANCE REQUIREMENTS	LG	KM
C	20/07/2020	GG	UPDATE TO ORCHARD MAINTENANCE REQUIREMENTS/WOODLAND	LG	KM
B	01/07/2020	GG	UPDATE TO POND LAYOUTS/SOUND BARRIER	LG	KM
A	01/05/2020	GG	FIRST ISSUE	LG	KM

DRAWING STATUS: S2 - FOR INFORMATION

3rd Floor, Kings Orchard, 1 Queen St, Bristol, BS2 0HQ, UK
T+44 (0) 1179 306 200
wsp.com

CLIENT: WSCC

ARCHITECT:

SITE PROJECT: A29

TITLE: SOFT LANDSCAPE PLAN
SHEET 2 OF 5

SCALE @ A1:	1:500	CHECKED:	LG	APPROVED:	KM
PROJECT NO:	70060779	DESIGNED:	GG	DRAWN:	GG
				DATE:	October 20



DRAWING No: A29-WSP-LA-GA-002

© WSP UK Ltd

File: \\uk-wsp\group\central_data\projects\70060779\WSP-LA-GA-002\WSP-LA-GA-002-LANDSCAPE_ARCHITECTURE_CAD\BIM\MODELS\DWG\LA-GA-001.dwg, 08 October 2020 10:45:08, by: G. Clarke, G. Clark

Reproduced from the Ordnance Survey map with the permission of the Controller of Her Majesty's Stationery Office. Licence no. 100046755. Crown copyright reserved.

SCALE 1:500



Specimen trees consisting of fruiting trees to offset loss from adjacent orchard.

Location indicative - please refer to acoustics and engineers drawings for further information

DO NOT SCALE

- NOTES:
1. ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
 2. DO NOT SCALE, IF IN DOUBT CONTACT WSP PROJECT MANAGER.
 3. THE WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE DFT MCHW, DMRB AND THE LOCAL REQUIREMENTS OF WEST SUSSEX COUNTY COUNCIL DESIGN GUIDE & SPECIFICATIONS.
 4. INDICATIVE LOCATIONS OF ARBORICULTURAL, ECOLOGICAL AND ACOUSTIC ELEMENTS.

KEY:

[Red dashed line]	Extent of works
[Red dotted line]	Extent of temporary land take
[Green hatched]	Temporary use land
[Green solid]	Hedge
[Green circle with cross]	Specimen Tree
[Green cross-hatched]	Shrub
[Green diagonal hatched]	Woodland Edge
[Green vertical hatched]	Woodland Core
[Green solid]	Amenity Grass Mix
[Light green solid]	Wildflower Meadow Grass Mix
[Blue solid]	Wetland Grass Mix
[Red hatched]	Areas to retain maximum feasible amount of existing vegetation where possible
[Purple line]	Root Protection Area - indicative location only
[Yellow triangle with 13]	Tree Preservation Order - indicative location only
[Red dashed line with triangles]	Acoustic Barrier - indicative location only

REV	DATE	BY	DESCRIPTION	CHK	APP
G	02/10/2020	GG	UPDATE TO LATEST HIGHWAYS LAYOUT & REDLINE BOUNDARY	LG	KM
F	20/08/2020	GG	UPDATE IN LINE WITH NEW POND AND HIGHWAYS LAYOUTS AND REDUCED WILDFLOWER MEADOW	LG	KM
E	06/08/2020	GG	UPDATE TO NEW DRAINAGE LAYOUT	LG	KM
D	21/07/2020	GG	UPDATE TO HEDGE MAINTENANCE REQUIREMENTS	LG	KM
C	20/07/2020	GG	UPDATE TO ORCHARD MAINTENANCE REQUIREMENTS/WOODLAND	LG	KM
B	01/07/2020	GG	UPDATE TO POND LAYOUTS/SOUND BARRIER	LG	KM
A	01/05/2020	GG	FIRST ISSUE	LG	KM

DRAWING STATUS: S2 - FOR INFORMATION



3rd Floor, Kings Orchard, 1 Queen St, Bristol, BS2 0HQ, UK
T+44 (0) 1179 306 200
wsp.com

CLIENT: WSCC

ARCHITECT: -

SITE/PROJECT: A29

TITLE: SOFT LANDSCAPE PLAN SHEET 3 OF 5

SCALE @ A1: 1:500	CHECKED: LG	APPROVED: KM
PROJECT NO: 70060779	DESIGNED: GG	DRAWN: GG
		DATE: October 20

DRAWING No: A29-WSP-LA-GA-003 REV: G


© WSP UK Ltd

File: \\uk.wsp.com\projects\70060779\A29\A29-LA-GA-003\A29-LA-GA-003-LANDSCAPE_ARCHITECTURE_CAD\BIM\MODELS\A29-LA-GA-003.dwg, amended on 08 October 2020 10:05:16 by Catherine Colman

Reproduced from the Ordnance Survey map with the permission of the Controller of Her Majesty's Stationary Office. Licence no. 100046755. Crown copyright reserved.
SCALE 1:500

REFER TO SHEET 2

REFER TO SHEET 4



DO NOT SCALE

- NOTES:
1. ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
 2. DO NOT SCALE, IF IN DOUBT CONTACT WSP PROJECT MANAGER.
 3. THE WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE DFT MCHW, DMRB AND THE LOCAL REQUIREMENTS OF WEST SUSSEX COUNTY COUNCIL DESIGN GUIDE & SPECIFICATIONS.
 4. INDICATIVE LOCATIONS OF ARBORICULTURAL, ECOLOGICAL AND ACOUSTIC ELEMENTS.

- KEY:
- Extent of works
 - Extent of temporary land take
 - Temporary use land
 - Hedge
 - Specimen Tree
 - Shrub
 - Woodland Edge
 - Amenity Grass Mix
 - Wildflower Meadow Grass Mix
 - Wetland Grass Mix
 - Areas to retain maximum feasible amount of existing vegetation where possible
 - Root Protection Area - indicative location only
 - Acoustic Barrier - indicative location only
 - Tree Preservation Order - indicative location only

Location indicative - please refer to acoustics and engineers drawings for further information.

REFER TO SHEET 3

REFER TO SHEETS 5

REV	DATE	BY	DESCRIPTION	CHK	APP
G	02/10/2020	GG	UPDATE TO LATEST HIGHWAYS LAYOUT & REDLINE BOUNDARY	LG	KM
F	20/08/2020	GG	UPDATE IN LINE WITH NEW POND AND HIGHWAYS LAYOUTS AND REDUCED WILDFLOWER MEADOW	LG	KM
E	06/08/2020	GG	UPDATE TO NEW DRAINAGE LAYOUT	LG	KM
D	21/07/2020	GG	UPDATE TO HEDGE MAINTENANCE REQUIREMENTS	LG	KM
C	20/07/2020	GG	UPDATE TO ORCHARD MAINTENANCE REQUIREMENTS/WOODLAND	LG	KM
B	01/07/2020	GG	UPDATE TO POND LAYOUTS/SOUND BARRIER	LG	KM
A	01/05/2020	GG	FIRST ISSUE	LG	KM

DRAWING STATUS: S2 - FOR INFORMATION

3rd Floor, Kings Orchard, 1 Queen St, Bristol, BS2 0HQ, UK
T+44 (0) 1179 306 200
wsp.com

CLIENT: WSCC

ARCHITECT:

SITE PROJECT: A29


TITLE: SOFT LANDSCAPE PLAN SHEET 4 OF 5

SCALE @ A1: 1:500	CHECKED: LG	APPROVED: KM
PROJECT NO: 70060779	DESIGNED: GG	DRAWN: GG
		DATE: October 20

DRAWING No: A29-WSP-LA-GA-004

© WSP UK Ltd

File: \\uk.wspgroup.com\central_data\projects\70060779\A29\WSP-LA-GA-004\A29-WSP-LA-GA-004.dwg
 Project: A29 - Kings Orchard
 Date: 02/10/2020 10:56:49
 Author: G. Colman
 Reproduced from the Ordnance Survey map with the permission of the Controller of Her Majesty's Stationary Office. Licence no. 100046755. Crown copyright reserved.





DO NOT SCALE

- NOTES:
1. ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
 2. DO NOT SCALE, IF IN DOUBT CONTACT WSP PROJECT MANAGER.
 3. THE WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE DFT MCHW, DMRB AND THE LOCAL REQUIREMENTS OF WEST SUSSEX COUNTY COUNCIL DESIGN GUIDE & SPECIFICATIONS.
 4. INDICATIVE LOCATIONS OF ARBORICULTURAL, ECOLOGICAL AND ACOUSTIC ELEMENTS.
 5. EXTENT AND PROPOSALS FOR FUTURE WORKS CURRENTLY UNKNOWN.
 6. AREA FOR COMPOUND INDICATIVE ONLY, CONTRACTOR TO DETAIL ALLOCATION, ACCESS AND ANY REMEDIAL GROUND WORKS

- KEY:
- Extent of works
 - Extent of temporary land take
 - Temporary use land
 - Hedge
 - Specimen Tree
 - Amenity Grass Mix
 - Wildflower Meadow Grass Mix
 - Wetland Grass Mix
 - Areas to retain maximum feasible amount of existing vegetation where possible
 - Root Protection Area - indicative location only

REV	DATE	BY	DESCRIPTION	CHK	APP
G	02/10/2020	GG	UPDATE TO LATEST HIGHWAYS LAYOUT & REDLINE BOUNDARY	LG	KM
F	20/08/2020	GG	UPDATE IN LINE WITH NEW POND AND HIGHWAYS LAYOUTS AND REDUCED WILDFLOWER MEADOW	LG	KM
E	06/08/2020	GG	UPDATE TO NEW DRAINAGE LAYOUT	LG	KM
D	21/07/2020	GG	UPDATE TO HEDGE MAINTENANCE REQUIREMENTS	LG	KM
C	20/07/2020	GG	UPDATE TO ORCHARD MAINTENANCE REQUIREMENTS/WOODLAND	LG	KM
B	01/07/2020	GG	UPDATE TO POND LAYOUTS/SOUND BARRIER	LG	KM
A	01/05/2020	GG	FIRST ISSUE	LG	KM

DRAWING STATUS: S4 - FOR CONSTRUCTION APPROVAL

wsp

3rd Floor, Kings Orchard, 1 Queen St, Bristol, BS2 0HQ, UK
T+44 (0) 1179 306 200
wsp.com

CLIENT: WSCC

ARCHITECT: -

SITE PROJECT: A29


TITLE: SOFT LANDSCAPE PLAN

SCALE @ A1: 1:500	CHECKED: LG	APPROVED: --
PROJECT NO: 70060779	DESIGNED: GG	DRAWN: GG
		DATE: October 20

DRAWING No: A29-WSP-LA-GA-005

© WSP UK Ltd

File: \\uk.wspgroup.com\central_data\projects\70060779\A29\WSP-LA-GA-001 - L1 - EMISSION & DING - 08 October 2020 10:46:20 by: Grahame, Graham
 Reproduced from the Ordnance Survey map with the permission of the Controller of Her Majesty's Stationary Office. Licence no. 100048755. Crown copyright reserved.



DO NOT SCALE

- NOTES:
1. ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
 2. DO NOT SCALE, IF IN DOUBT CONTACT WSP PROJECT MANAGER.
 3. THE WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE DFT MCHW, DMRB AND THE LOCAL REQUIREMENTS OF WEST SUSSEX COUNTY COUNCIL DESIGN GUIDE & SPECIFICATIONS.
 4. INDICATIVE LOCATIONS OF ARBORICULTURAL, ECOLOGICAL AND ACOUSTIC ELEMENTS.

- KEY:
- Extent of works
 - Extent of temporary land take
 - Temporary use land
 - Existing Vegetation
 - Specimen Tree
 - Shrub
 - Woodland Edge
 - Woodland Core
 - Amenity Grass Mix
 - Wildflower Meadow Grass Mix
 - Wetland Grass Mix
 - Areas to retain maximum feasible amount of existing vegetation where possible
 - Root Protection Area - indicative location only
 - Tree Preservation Order - indicative location only

REV	DATE	BY	DESCRIPTION	CHK	APP
G	02/10/2020	GG	UPDATE TO LATEST HIGHWAYS LAYOUT & REDLINE BOUNDARY	LG	KM
F	20/08/2020	GG	UPDATE IN LINE WITH NEW POND AND HIGHWAYS LAYOUTS AND REDUCED WILDFLOWER MEADOW	LG	KM
E	06/08/2020	GG	UPDATE TO NEW DRAINAGE LAYOUT	LG	KM
D	21/07/2020	GG	UPDATE TO HEDGE MAINTENANCE REQUIREMENTS	LG	KM
C	20/07/2020	GG	UPDATE TO ORCHARD MAINTENANCE REQUIREMENTS/WOODLAND	LG	KM
B	01/07/2020	GG	UPDATE TO POND LAYOUTS/SOUND BARRIER	LG	KM
A	01/05/2020	GG	FIRST ISSUE	LG	KM

DRAWING STATUS: S2 - FOR INFORMATION

wsp

3rd Floor, Kings Orchard, 1 Queen St, Bristol, BS2 0HQ, UK
T+44 (0) 1179 306 200
wsp.com

CLIENT: WSCC

ARCHITECT: -

SITE/PROJECT: A29

TITLE: ECOLOGICAL MITIGATION PLAN SHEET 1 OF 5

SCALE @ A1: 1:500	CHECKED: LG	APPROVED: KM
PROJECT NO: 70060779	DESIGNED: GG	DRAWN: GG
		DATE: October 20


DRAWING No: A29-WSP-LA-GA-001

© WSP UK Ltd

File: A29-WSP-LA-GA-001-ECOLOGICAL MITIGATION PLAN SHEET 1 OF 5.dwg
 Project: A29 - WSCC
 Date: 02/10/2020 10:42:40
 Author: G. Cohen

Reproduced from the Ordnance Survey map with the permission of the Controller of Her Majesty's Stationary Office. Licence no. 100048755. Crown copyright reserved.

SCALE: 1:500



DO NOT SCALE

- NOTES:
1. ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
 2. DO NOT SCALE, IF IN DOUBT CONTACT WSP PROJECT MANAGER.
 3. THE WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE DFT MCHW, DMRB AND THE LOCAL REQUIREMENTS OF WEST SUSSEX COUNTY COUNCIL DESIGN GUIDE & SPECIFICATIONS.
 4. INDICATIVE LOCATIONS OF ARBORICULTURAL, ECOLOGICAL AND ACOUSTIC ELEMENTS.

KEY:

- Extent of works
- Extent of temporary land take
- Temporary use land
- Existing Vegetation
- Hedge
- Specimen Tree
- Shrub
- Woodland Edge
- Woodland Core
- Amenity Grass Mix
- Wildflower Meadow Grass Mix
- Wetland Grass Mix
- Areas to retain maximum feasible amount of existing vegetation where possible
- Root Protection Area - indicative location only
- Tree Preservation Order - indicative location only
- Proposed Bench

REV	DATE	BY	DESCRIPTION	CHK	APP
G	02/10/2020	GG	UPDATE TO LATEST HIGHWAYS LAYOUT & REDLINE BOUNDARY	LG	KM
F	20/08/2020	GG	UPDATE IN LINE WITH NEW POND AND HIGHWAYS LAYOUTS AND REDUCED WILDFLOWER MEADOW	LG	KM
E	06/08/2020	GG	UPDATE TO NEW DRAINAGE LAYOUT	LG	KM
D	21/07/2020	GG	UPDATE TO HEDGE MAINTENANCE REQUIREMENTS	LG	KM
C	20/07/2020	GG	UPDATE TO ORCHARD MAINTENANCE REQUIREMENTS/WOODLAND	LG	KM
B	01/07/2020	GG	UPDATE TO POND LAYOUTS/SOUND BARRIER	LG	KM
A	01/05/2020	GG	FIRST ISSUE	LG	KM

DRAWING STATUS: S2 - FOR INFORMATION

3rd Floor, Kings Orchard, 1 Queen St, Bristol, BS2 0HQ, UK
T+44 (0) 1179 306 200
wsp.com

CLIENT: WSCC

ARCHITECT:

SITE PROJECT: A29

ECOLOGICAL MITIGATION PLAN SHEET 2 OF 5

SCALE @ A1: 1:500	CHECKED: LG	APPROVED: KM
PROJECT NO: 70060779	DESIGNED: GG	DRAWN: GG
DATE: October 20		

DRAWING No: A29-WSP-LA-GA-002

REV: G

© WSP UK Ltd

File: \\uk-wsp\group_data\projects\A29\PROJECTS\30060779\B0079_WSCC_A29_PHASE1_PLANNING_ARCHITECTURAL\LA\GA-001_LANDSCAPE_ARCHITECTURAL\CAD\BIM\MODELS\LA\GA-001_ARCHITECTURAL\DWG_06\06_2020_10_01_09.dwg
 Author: G. Gribble, G. Gribble, G. Gribble
 Date: 06/10/2020 10:01:09
 Reproduced from the Ordnance Survey map with the permission of the Controller of Her Majesty's Stationary Office. Licence no. 100048755. Crown copyright reserved.



Proposed artificial badger sett location


Indicative Refugia/Hibernacula

Indicative Bat Box Location

Indicative Bird Box Location

REFER TO SHEET 1

REFER TO SHEET 3





DO NOT SCALE

- NOTES:
1. ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
 2. DO NOT SCALE, IF IN DOUBT CONTACT WSP PROJECT MANAGER.
 3. THE WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE DFT MCHW, DMRB AND THE LOCAL REQUIREMENTS OF WEST SUSSEX COUNTY COUNCIL DESIGN GUIDE & SPECIFICATIONS.
 4. INDICATIVE LOCATIONS OF ARBORICULTURAL, ECOLOGICAL AND ACOUSTIC ELEMENTS.

KEY:

	Extent of works
	Extent of temporary land take
	Temporary use land
	Hedge
	Specimen Tree
	Shrub
	Woodland Edge
	Woodland Core
	Amenity Grass Mix
	Wildflower Meadow Grass Mix
	Wetland Grass Mix
	Areas to retain maximum feasible amount of existing vegetation where possible
	Root Protection Area - indicative location only
	Tree Preservation Order - indicative location only
	Acoustic Barrier - indicative location only

REV	DATE	BY	DESCRIPTION	CHK	APP
G	02/10/2020	GG	UPDATE TO LATEST HIGHWAYS LAYOUT & REDLINE BOUNDARY	LG	KM
F	20/08/2020	GG	UPDATE IN LINE WITH NEW POND AND HIGHWAYS LAYOUTS AND REDUCED WILDFLOWER MEADOW	LG	KM
E	06/08/2020	GG	UPDATE TO NEW DRAINAGE LAYOUT	LG	KM
D	21/07/2020	GG	UPDATE TO HEDGE MAINTENANCE REQUIREMENTS	LG	KM
C	20/07/2020	GG	UPDATE TO ORCHARD MAINTENANCE REQUIREMENTS/WOODLAND	LG	KM
B	01/07/2020	GG	UPDATE TO POND LAYOUTS/SOUND BARRIER	LG	KM
A	01/05/2020	GG	FIRST ISSUE	LG	KM

DRAWING STATUS: S2 - FOR INFORMATION

wsp

3rd Floor, Kings Orchard, 1 Queen St, Bristol, BS2 0HQ, UK
T+44 (0) 1179 306 200
wsp.com

CLIENT: WSCC

ARCHITECT: -

SITE/PROJECT: A29

TITLE: ECOLOGICAL MITIGATION PLAN SHEET 3 OF 5

SCALE @ A1: 1:500	CHECKED: LG	APPROVED: KM
PROJECT NO: 70060779	DESIGNED: GG	DRAWN: GG
DATE: October 20		REV: G

DRAWING No: A29-WSP-LA-GA-003


© WSP UK Ltd

File: \\uk-wsp\group\central_data\projects\70060779\70060779_01\SCC_002_PHASE1_PLANNING_ARCHITECTURE\WSP_LANDSCAPE_ARCHITECTURE\PROJECTS\CAD\BIM\MODELS\3D\WSP_LA-GA-003_1_000048755.dwg, 08 October 2020 10:45:16, by: G. Cohen
 Reproduced from the Ordnance Survey map with the permission of the Controller of Her Majesty's Stationary Office. Licence no. 100048755. Crown copyright reserved.

SCALE 1:500

REFER TO SHEET 4

REFER TO SHEET 2



DO NOT SCALE

- NOTES:
- ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
 - DO NOT SCALE, IF IN DOUBT CONTACT WSP PROJECT MANAGER.
 - THE WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE DFT MCHW, DMRB AND THE LOCAL REQUIREMENTS OF WEST SUSSEX COUNTY COUNCIL DESIGN GUIDE & SPECIFICATIONS.
 - INDICATIVE LOCATIONS OF ARBORICULTURAL, ECOLOGICAL AND ACOUSTIC ELEMENTS.

- KEY:
- Extent of works
 - Extent of temporary land take
 - Temporary use land
 - Hedge
 - Specimen Tree
 - Shrub
 - Woodland Edge
 - Amenity Grass Mix
 - Wildflower Meadow Grass Mix
 - Wetland Grass Mix
 - Areas to retain maximum feasible amount of existing vegetation where possible
 - Root Protection Area - indicative location only
 - Acoustic Barrier - indicative location only
 - Tree Preservation Order - indicative location only

REV	DATE	BY	DESCRIPTION	CHK	APP
G	02/10/2020	GG	UPDATE TO LATEST HIGHWAYS LAYOUT & REDLINE BOUNDARY	LG	KM
F	20/08/2020	GG	UPDATE IN LINE WITH NEW POND AND HIGHWAYS LAYOUTS AND REDUCED WILDFLOWER MEADOW	LG	KM
E	06/08/2020	GG	UPDATE TO NEW DRAINAGE LAYOUT	LG	KM
D	21/07/2020	GG	UPDATE TO HEDGE MAINTENANCE REQUIREMENTS	LG	KM
C	20/07/2020	GG	UPDATE TO ORCHARD MAINTENANCE REQUIREMENTS/WOODLAND	LG	KM
B	01/07/2020	GG	UPDATE TO POND LAYOUTS/SOUND BARRIER	LG	KM
A	01/05/2020	GG	FIRST ISSUE	LG	KM

DRAWING STATUS: S2 - FOR INFORMATION

wsp

3rd Floor, Kings Orchard, 1 Queen St, Bristol, BS2 0HQ, UK
T+ 44 (0) 1179 306 200
wsp.com

CLIENT: WSCC

ARCHITECT:

SITE PROJECT: A29

TITLE: ECOLOGICAL MITIGATION
PLAN SHEET 4 OF 5


SCALE @ A1:	1:500	CHECKED:	LG	APPROVED:	KM
PROJECT NO:	70060779	DESIGNED:	GG	DRAWN:	GG
DATE:	October 20				

DRAWING No: A29-WSP-LA-GA-004

© WSP UK Ltd

File path: \\uk-wsp\groups\central_data\projects\70060779\70060779-1\SCC-102\PHASE 1 PLANNING\PROJ\CD\WSP\LA-GA-004\WSP-LA-GA-004-1.ecad.dwg 08 October 2020 10:55:49 by Grahame Gibson

Reproduced from the Ordnance Survey map with the permission of the Controller of Her Majesty's Stationary Office. Licence no. 100048755. Crown copyright reserved.





DO NOT SCALE

- NOTES:
1. ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
 2. DO NOT SCALE, IF IN DOUBT CONTACT WSP PROJECT MANAGER.
 3. THE WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE DFT MCHW, DMRB AND THE LOCAL REQUIREMENTS OF WEST SUSSEX COUNTY COUNCIL DESIGN GUIDE & SPECIFICATIONS.
 4. INDICATIVE LOCATIONS OF ARBORICULTURAL, ECOLOGICAL AND ACOUSTIC ELEMENTS.
 5. EXTENT AND PROPOSALS FOR FUTURE WORKS CURRENTLY UNKNOWN.
 6. AREA FOR COMPOUND INDICATIVE ONLY, CONTRACTOR TO DETAIL ALLOCATION, ACCESS AND ANY REMEDIAL GROUND WORKS

- KEY:
- Extent of works
 - Extent of temporary land take
 - Temporary use land
 - Hedge
 - Specimen Tree
 - Amenity Grass Mix
 - Wildflower Meadow Grass Mix
 - Wetland Grass Mix
 - Areas to retain maximum feasible amount of existing vegetation where possible
 - Root Protection Area - indicative location only

REV	DATE	BY	DESCRIPTION	CHK	APP
G	02/10/2020	GG	UPDATE TO LATEST HIGHWAYS LAYOUT & REDLINE BOUNDARY	LG	KM
F	20/08/2020	GG	UPDATE IN LINE WITH NEW POND AND HIGHWAYS LAYOUTS AND REDUCED WILDFLOWER MEADOW	LG	KM
E	06/08/2020	GG	UPDATE TO NEW DRAINAGE LAYOUT	LG	KM
D	21/07/2020	GG	UPDATE TO HEDGE MAINTENANCE REQUIREMENTS	LG	KM
C	20/07/2020	GG	UPDATE TO ORCHARD MAINTENANCE REQUIREMENTS/WOODLAND	LG	KM
B	01/07/2020	GG	UPDATE TO POND LAYOUTS/SOUND BARRIER	LG	KM
A	01/05/2020	GG	FIRST ISSUE	LG	KM

DRAWING STATUS: S4 - FOR CONSTRUCTION APPROVAL

3rd Floor, Kings Orchard, 1 Queen St, Bristol, BS2 0HQ, UK
T+44 (0) 1179 306 200
wsp.com

CLIENT: WSCC

ARCHITECT: -

SITE PROJECT: A29

TITLE: ECOLOGICAL MITIGATION PLAN SHEET 5 OF 5

SCALE @ A1: 1:500	CHECKED: LG	APPROVED: --
PROJECT NO: 70060779	DESIGNED: GG	DRAWN: GG
		DATE: October 20

DRAWING No: A29-WSP-LA-GA-005

© WSP UK Ltd

File: \\uk-wsp\group\central_data\projects\70060779\B0779_WSCC - S4 PHASE 1 PLANNING ARCHITECTURE\WSP LA GA-001 - LEBSON & DING - 08 October 2020 10:46:20 by Garkner, Coban

Reproduced from the Ordnance Survey map with the permission of the Controller of Her Majesty's Stationary Office. Licence no. 100048755. Crown copyright reserved.

SCALE 1:500

Appendix A

RELEVANT LEGISLATION



ENGLAND AND WALES LEGISLATION AND POLICY CONTEXT

This report has been compiled with reference to relevant wildlife legislation, planning policy and the UK Biodiversity Framework. An overview and context of relevant legislation is provided, with the relevant protection each species groups or species receives summarised in Table 1.

The Wildlife and Countryside Act 1981, (as amended) (WCA)

Protected birds, animals and plants are listed under Schedules 1, 5, 8 and 9 respectively of the WCA, a description of these Schedules and their meaning is provided below.

Under the WCA (England and Wales) all birds, their nests and eggs (with exception of species listed under Schedule 2) are protected by the WCA. It is an offence to:

- Intentionally kill, injure, or take any wild bird,
- Take or destroy an egg of any wild bird.
- Damage or destroy the nest of any wild bird (whilst being built, or in use). Under the WCA the clearance of vegetation within the survey area boundary, or immediately adjacent to the survey area during the bird nesting season could result in an offence occurring by the disruption or destruction of nest sites. The bird breeding season can be taken to occur between March - August inclusive, although is subject to variations based on species, geographical and seasonal factors.

Schedule 1

Birds listed under Schedule 1 of the WCA⁵ are afforded additional protection with regard to intentional or reckless disturbance whilst nest-building, or at a nest containing eggs or young, or disturb the dependent young of such a bird.

Schedule 5

Species listed in Schedule 5 can either be fully protected or be partially protected under Section 9, which makes it unlawful to intentionally:

- Part 1: kill, injure or take;
- Part 2: possess or control (live or dead animal, part or derivative);
- Part 4 (a): damage or destruct any structure used for shelter or protection;
- Part 4 (b): disturb them in a place of shelter or protection;
- Part 4 (c): obstruct access to place of shelter or protection;
- Part 5 (a): sell, offer for sale, possess or transport for the purpose of sale (live or dead animal, part or derivative);
- Part 5 (b): advertise for buying or selling.

⁵ To view the current list of Schedule 1 listed birds visit:

<http://www.legislation.gov.uk/ukpga/1981/69/schedule/1> [Accessed 01.03.2017].

Schedule 8

The Act makes it an offence (subject to exceptions) to pick, uproot, trade in, or possess (for the purposes of trade) any wild plant listed in Schedule 8, and prohibits the unauthorised intentional uprooting of such plants.

Schedule 9

Invasive species listed under Schedule 9 are prohibited from release into the wild and the Act prohibits planting or “causing to grow” in the wild of any plant species listed in Schedule 9. It should be noted that certain bird species listed on Schedule 1 of the WCA are also listed on Schedule 9 to prevent release of non-native and captive individuals, this includes barn owl, red kite, goshawk and corncrake.

Countryside Rights of Way Act 2000 (CRoW Act)

The CRoW Act has amended the WCA in England and Wales strengthening the protection afforded to Sites of Special Scientific Interest (SSSI) and the legal protection for threatened species. It adds the word ‘reckless’ to the wording of the offences listed under Section 9(4) of the WCA. This alteration makes it an offence to recklessly commit an offence, where previously an offence had to be intentional to result in a breach of legislation.

Natural Environment and Rural Communities (NERC) Act 2006

Species and Habitats of Principal Importance in England and Wales are listed under Section 41 and Section 42 respectively of the NERC Act. The Section 41 and 42 lists detail species that are of principal importance for the conservation of biodiversity in England and Wales, and should be used to guide decision-makers such as local and regional authorities when implementing their duty to have regard for the conservation of biodiversity in the exercise of their normal functions – as required under Section 40 of the NERC Act 2006.

The Environment (Wales) Act 2016

The Environment (Wales) Act 2016 (<http://www.legislation.gov.uk/anaw/2016/3/contents/enacted>) puts in place the legislation needed to plan and manage Wales’ natural resources in a more proactive, sustainable and cohesive way. Section 7 replaces the duty in Section 42 of the NERC Act 2006 and it places a duty on the Welsh Ministers to publish, review and revise lists of living organisms and types of habitats which they consider are of key significance to sustain and improve biodiversity in Wales. The species and habitat lists are identical to those in Section 42 but it should be noted it is currently under review (23.03.2017).

The Protection of Badgers Act (1992)

It is an offence to wilfully take, kill, injure, possess or ill-treat a badger. Under the Act their setts are protected against intentional or reckless interference. Sett interference includes damaging or destroying a sett, obstructing access to any part of the sett, or disturbance of a badger whilst it is occupying a sett. The Act defines a badger sett as ‘any structure or place, which displays signs indicating the current use by a badger’ and Natural England (NE) takes this definition to include

seasonally used setts that are not occupied but that show sign of recent use by badgers (Natural England, 2009⁶).

If impacts to badgers or their setts are unavoidable then authorised sett disturbance requires a licence.

The UK Post-2010 Biodiversity Framework (2011-2020) (JNCC and DEFRA, 2012)

This Framework lists the UK's most threatened species and habitats and sets out targets and objectives for their management and recovery. The UK Biodiversity Action Plan (BAP) process is delivered nationally, regionally and locally and should be used as a guide for decision-makers to have regards for the targets set by the framework and the goals they aim to achieve. The UK BAP has now been replaced by the UK Post-2010 Biodiversity Framework, however, it contains useful information on how to characterise important species assemblages and habitats which is still relevant (UK Post-2010 Biodiversity Framework, 2012⁷).

The Conservation of Habitats and Species Regulations 2017

The Conservation of Habitats and Species Regulations 2017 consolidate the Conservation of Habitats and Species Regulations 2010 with subsequent amendments. The Regulations transpose Council Directive 92/43/EEC, on the conservation of natural habitats and of wild fauna and flora (EC Habitats Directive), into national law. They also transpose elements of the EU Wild Birds Directive in England and Wales. The Regulations came into force on 30th November 2017, and extend to England and Wales (including the adjacent territorial sea) and to a limited extent in Scotland (reserved matters) and Northern Ireland (excepted matters). In Scotland, the Habitats Directive is transposed through a combination of the Habitats Regulations 2010 (in relation to reserved matters) and the Conservation (Natural Habitats andc.) Regulations 1994. The Conservation (Natural Habitats, andc) Regulations (Northern Ireland) 1995 (as amended) transpose the Habitats Directive in relation to Northern Ireland.

All species listed under Annex IV of the Habitats Directive require strict protection and are known as European Protected Species (EPS). Under Regulation 42 of the Habitats Regulations it is unlawful to:

- Deliberately kill, capture or disturb;
- Deliberately take or destroy the eggs of; and
- Damage or destroy the breeding site/resting place of any species protected under this legislation.

If the Ecologist determines that impacts to an EPS are unavoidable then the works may need to be carried out under a site specific mitigation licence from Natural England (NE) or Natural Resources

⁶ Natural England, June 2009, Protection of Badgers Act 1992 (as amended), Guidance on 'Current Use' in the definition of a Badger Sett WMLG17, Natural England, Peterborough.

⁷ JNCC and Defra (on behalf of the Four Countries' Biodiversity Group), July 2012, UK Post-2010 Biodiversity Framework, Available from: http://jncc.defra.gov.uk/pdf/UK_Post2010_Bio-Fwork.pdf [Accessed 02.03.2017].



Wales (NRW). Low Impact Class licences are also available in both England and Wales for bats and great crested newts. This enables Registered Low Impact Consultants to undertake certain low impact activities reducing the EPS application paperwork and process length.

Certain EPS are also listed under Annex II of the Habitats Directive and are afforded protection by the establishment of core areas of habitat known as Special Areas of Conservation. This means these species are a relevant consideration in a Habitats Regulations Assessment (HRA).

The Birds Directive seeks to maintain populations of all wild bird species across their natural range (Article 2). All bird species listed under Annex I⁸ of the Birds Directive are rare or vulnerable and afforded protection by the classification of Special Protection Areas (SPAs), these are also designated under all regularly occurring migratory species, with regard to the protection of wetlands of international importance (Article 4). This means these bird species and communities are a relevant consideration in HRA.

National Planning Policy Framework NPPF

The NPPF states the following in respect of biodiversity protection under Section 11 Conserving and enhancing the natural environment;

'The planning system should contribute to and enhance the natural and local environment by:

- protecting and enhancing valued landscapes, geological conservation interests and soils*
- recognising the wider benefits of ecosystem services*
- minimising impacts on biodiversity and providing net gains in biodiversity where possible, contributing to the Government's commitment to halt the overall decline in biodiversity, including by establishing coherent ecological networks that are more resilient to current and future pressures.'*

West Sussex Transport Plan (2011)

The West Sussex Transport Plan (2011) was subject to a Strategic Environmental Assessment (SEA) at the time of publishing which identified that;

'Mitigation is required to avoid negative impacts on biodiversity. This will include using green infrastructure to improve the connectivity of hedge lines to reconnect habitats, for example a 'Notable Verge' strategy is already in place;

and

The impact of the [Local Transport Plan] is dependent on taking opportunities to improve green infrastructure, particularly in new development, and in the [South Downs National Park] where existing green infrastructure can be disjointed.'

⁸ To view birds listed under Annex I visit:

http://ec.europa.eu/environment/nature/conservation/wildbirds/threatened/index_en.htm [Accessed: 06.04.2017]

West Sussex Structure Plan (2005)

The West Sussex Structure Plan (WSCC 2005) has no formal status, however ‘*Though the Plan has no formal status in the current planning system, it remains our strategic policy statement for future development and land-use planning*’⁹. Policy ERA2 relates to Nature Conservation, stating;

‘(a) Development should not be permitted unless the wide range of habitats, species and geological features of the County will be protected, conserved and, where possible, enhanced particularly through long-term management mechanisms and habitat creation schemes. A particularly high level of protection should be afforded to sites and features of national and international importance. Proposals for the extension or creation of new habitats should be permitted provided that they are consistent with wider environmental objectives.

(b) Local plans will include policies to:

(1) ensure that site evaluation is undertaken to establish the nature conservation importance of proposed development sites;

(2) protect sites or features of nature conservation importance, including those protected under legislation and prevent development unless there are no alternative solutions and there are overriding reasons which outweigh the need to safeguard the value of sites or features;

(3) ensure that where development would result in the loss of an important nature conservation resource, a new resource is provided which is of at least equivalent value, where possible;

(4) where appropriate, secure the restoration, creation and management of habitats through development proposals; and

(5) where necessary, ensure the investigation and recording of sites and features of nature conservation importance, and, where appropriate, the preservation of any finds.’

Adopted Arun Local Plan (Arun DC, 2018)

The Adopted Arun Local Plan (Arun DC, 2018) contains a number of policies relating to biodiversity, of which Policy ENV SP1 Natural Environment and Policy ENV DM5 Development and Biodiversity are the most pertinent.

Policy ENV SP1, Natural Environment states:

‘Arun District Council will encourage and promote the preservation, restoration and enhancement of biodiversity and the natural environment through the development process and particularly through policies for the protection of both designated and non-designated sites. Where possible it shall also promote the creation of new areas for habitats and species. In relation to designated sites,

⁹ <https://www.westsussex.gov.uk/about-the-council/policies-and-reports/environment-planning-and-waste-policy-and-reports/structure-plan/>



development will be permitted where it protects sites listed in Tables 17.1-17.6 that are recognised for the species and habitats contained within them.'

Policy ENV DM5 Development and Biodiversity states:

'Development schemes shall, in the first instance, seek to achieve a net gain in biodiversity and protect existing habitats on site. They shall also however incorporate elements of biodiversity including green walls, roofs, bat and bird boxes as well as landscape features minimising adverse impacts on existing habitats (whether designated or not). Development schemes shall also be appropriately designed to facilitate the emergence of new habitats through the creation of links between habitat areas and open spaces. Together, these provide a network of green spaces which serve to reconnect isolated sites and facilitate species movement.

Where there is evidence of a protected species on a proposed development site, planning applications shall include a detailed survey of the subject species, with details of measures to be incorporated into the development scheme to avoid loss of the species. This involves consideration of any impacts that will affect the species directly or indirectly, whether within the application site or in an area outside of the site, which may be indirectly affected by the proposals. All surveys shall be carried out at an appropriate time of year and shall be undertaken by a qualified and, where appropriate, suitably licensed person.

All developments shall have regard to Natural England's standing advice for protected species.'



Mountbatten House
Basing View
Basingstoke, Hampshire
RG21 4HJ

wsp.com