

2. All dead or damaged plants shall be replaced in accordance with the initial spec

3. Firming - Plants shall be inspected during each visit to undertake maintenance ope ions and any which have been subject to frost heave or wind rock shall be straightened to an upright position and the ground re-firmed. 4. Stakes, tubes, guards and their ties shall be inspected twice per year in October and March, and adjusted to allow

for the growth of each plant. Any damaged items shall be removed off Site and replaced with new items.


5. Stakes, tubes, guards and ties shall be removed from plants where they are no longer required and disposed of off site

6. Weed Control within planted areas - Plant circles shall be defined as the area within a 500 mm radius of an individual tree or shrub, within which weed control operations are carried out. Translocated herbicides shall be applied to the plant circles around individual trees and using a shield to protect the plants from the herbicide. The operation shall include the clearance of vegetation by hand from within shelters and guards.


## **5 YEAR AFTERCARE PERIOD**

Following planting works, a period of 5 years aftercare management and monitoring shall be undertaken. The aftercare period shall run concurrently with the 12 month Maintenance / Establishment Period (above).

Hedgerow planting- during the first 12 month period maintenance operations will be as above. Thereafter the new hedge will be maintained to a clipped height of 1.5m. Remaining stakes / guards will be removed. Weed control will be carried out until the plants no longer compete. Failed stock will be replaced as instructed.



Site Boundary Proposed Hedgerow Mix A




Proposed timber post and strained wire fence

> 38.56 available. Level information taken from historic drawing 'Existing Site Character Figure 4 A'

Existing retained tree

Existing retained hedgerow

Existing retained woodland



## NICHOLAS PEARSON ASSOCIATES

Environmental Planners · Landscape Architects · Ecologists

Client **IGAS ENERGY** 

## Project STORRINGTON OIL WELL SITE, PULBOROUGH ROAD COOTHAM, STORRINGTON, WEST SUSSEX

Drawing STORRINGTON OIL WELL SITE SUPPLEMENTARY LANDSCAPE PROPOSALS PLAN WSCC/050/13/SR PLANNING CONDITION 18

Drawing No. NPA	10705 501	Scale 1:500@AI		Date DEC 2013
Rev <b>P02</b>	Drawn RG	Checked TB	Approved SM	Status PLANNING

			50m							© Nicholas Pearson Associates Ltd. Head Office : 30 Brock Street Bath BA1 2LN United Kingdom Tel : + 44 (0) 1225 445548 Fax + 44 (0) 1225 312387 www.npaconsult.co.uk
	0	25m		P02	EH	M SM	м	Maintenance details updated	27.06.2014	
				POI	SJM S	M SM	м	Client amendments		All discrepancies or queries regarding this drawing should be referred to Nicholas Pearson Associates Ltd. Nicholas Pearson Associates Ltd accept no liability for any expense, loss or damage of whatsoever nature and however arising from any variation made
				Rev	Drawn Ch	cked Appro	oved De	Description		to this drawing or in the execution of the work to which it relates which has not been referred to them and their approval obtained.
Reproduced from the Ordnance Survey's map with the permission of the Controller of The Stationery Office, © Crown Copyright. Licence No. 100018702									Dwg Ref: N:\Projects\10705 IG\Work\500 Softworks\NPA 10705 501.dwg	

Plotted on 6/27/2014 by Eleanor Hall, Plotscale: 1:1, Paper Size ISO full bleed AI (594.00 x 841.00 MM), Plot style: NPA\_ISO.ctb